



PN	TRUSS HEIGHT	DIM "A"	DIM "B"	DIM "C"	DIM "D"
3102-32	32' to 32.99' [9.75-10.05M]	10'-3" [3.12M]	18'-6" [5.64M]	13'-2 1/2" [4.03M]	21'-8" [6.60M]
3102-33	33' to 33.99' [10.06-10.35M]	10'-9" [3.28M]	19'-6" [5.94M]	13'-2 1/2" [4.03M]	22'-8" [6.91M]
3102-34	34 to 34.99' [10.36-10.66M]	11'-2" [3.40M]	20'-6" [6.25M]	13'-2 1/2" [4.03M]	23'-8" [7.21M]
3102-35	35' to 35.99' [10.67-10.96M]	11'-8" [3.56M]	21'-6" [6.55M]	13'-2 1/2" [4.03M]	24'-8" [7.52M]

F	WDC	08-01-19
E	WDC	06-25-13
REV	BY	DATE




Gared Holdings, LLC
9200 E. 146th St. Noblesville, IN 46060

THIS DOCUMENT CONTAINS TRADE SECRET AND OTHER MATERIALS WHICH ARE PROTECTED BY CONFIDENTIALITY NOTICE AND AGREEMENT AND BY COPYRIGHT. ANY USE OR COPYING OF THIS DOCUMENT EXCEPT AS AUTHORIZED BY GARED HOLDINGS, LLC IS STRICTLY PROHIBITED.

CLAMPED REAR BRACED FRONT FOLDING

DRAWN CROSBY		DATE 6/25/2013	DATE ISSUED
APPROVED		DATE	

FILE LOC. Q:\Inventor Files\Specification Files\03_Single Post\3102

SIZE A	SCALE	SHT. NO. 1 OF 2	PART NO. 3102	REV F
--------	-------	-----------------	---------------	-------



Model 3102

Clamped Single Post, Rear Braced, Front Folding, Basketball Backstop

Recommended Application

This model is designed for those areas allowing sufficient space behind the backboard for a rear brace. This single post unit can be used at heights from 32' to 36'.

Overhead Structure

Unit shall be supported from 3-1/2" O.D. x 0.120" wall ASTM A-500 Grade B horizontal and 2-3/8" O.D. x 14 gauge (0.083") wall ASTM A-500 Grade B vertical structural steel tubing secured to the building with heavy gauge steel stampings or weldments (as required by building conditions). When truss span widths exceed 10'-0", 3-1/2" O.D. x Schedule 40 (0.216") wall ASTM A-500 Grade B may be used for the horizontals. Spans over 14'-0" may use welded bridge pipe.

Backstop

The backstop shall be of a single post design with a main vertical mast constructed of 6-5/8" O.D. x 0.120" wall ASTM A-513 structural steel tubing with 2-3/8" O.D. x 14 gauge (0.083") wall ASTM A-500 Grade B steel tube sway braces clamped in place. Main mast will be suspended from superstructure with a welded steel plate offset hanger 4" in front of the pivot point, less than 4" will not be approved as equal. Backstop shall be manufactured to allow 3" vertical adjustment for plumbing of the backboard. All fittings shall be heavy gauge steel stampings or weldments. A direct goal attachment is used to transfer stress from the goal to the main mast assembly preventing strain on the backboard.

Rear brace shall be 2-3/8" O.D. x 14 gauge (0.083") wall ASTM A-500 Grade B steel tubing with a welded 1x2 reinforcement tube. It shall be attached to the mast at a height 12" to 18" above the bottom of the mast pipe with a slide mechanism and steel bushing for travel on a 1-7/8" O.D. slide rod. The entire assembly shall be self-aligning and designed to be self-locking and self-releasing. Backstop shall be raised and lowered with 1/4" galvanized aircraft cable with a breaking strength of 7000 lbs. Cable automatically retracts by means of a 1/8" diameter cable connected to counter weight concealed in the mast tube. Backstop manufactured in accordance with 1994 rule 1, section 8, stating that all parts of the backboard support system shall be at least 6" behind backboard.

All steel has a black powder coat finish, standard. Optional colors are available.

Accessories

Backboards and Goals - See the backboards and goals section in the specification manual.

Backboard Padding - See the accessories section in the specification manual.

Hoists - Electric hoist or manual winch is available on all folding units. See the accessories section in the specification manual.

Safstop Safety Locking Strap - See the accessories section in the specification manual.

Certifications

Unit meets all requirements of the NCAA and NFHS. Unit complies with design standards of the California Department of State Architects. Unit is approved by FIBA for international Level 2 competition. Certificate of Approval available.



Subject to design change and current manufacturing practices.